

イ 簡易水道

市町村名	水道事業名	経営 区分	創設時 給水開始 年月	最新認可 年月日	人口			原水 種別	浄水施設		配水池		計画 1日最大 取水量 (m ³ /日)	1日最大給水量 (m ³ /日)		実績 1日平均 給水量 (m ³ /日)
					計画	現在								計画値	実績値	
					給水	給水 区域内	給水		処理能力 (m ³ /日)	浄水方法	池 数	容量				
那須町	平和郷	私	S45.10	H5.12.28	1,400	920	920	浅	350	消毒のみ	1	100	720	350	350	165
那須町	平和台	私	S46.10	H5.12.28	400	520	520	浅	230	消毒のみ	1	100	230	100	127	95
	那珂川水系				1,800	1,440	1,440		580		2	200	950	450	477	260
日光市	日光二社一寺	私	T15.6	T14.7.23	700	400	155	伏・自	3,800	緩速ろ過	2	360	4,000	3,800	1,879	1,667
	鬼怒川水系				700	400	155		3,800		2	360	4,000	3,800	1,879	1,671
鹿沼市	ヒルタウンさつき野	組	H4.2	H14.11.7	3,073	2,032	2,032	深	1,500	消毒のみ	2	854	1,480	1,100	735	590
	渡良瀬川水系				3,073	2,032	2,032		1,500		2	854	1,480	1,100	735	591
	合　　計				5,573	3,872	3,627		5,880		6	1,414	6,430	5,350	3,091	2,522

水道事業名	水源の種別・実績年間取水量（m ³ ／年）								実績年間水量（m ³ ／年）							
	ダム	湖水	自流	伏流水	浅井戸	深井戸	浄水 受水	その他	取水量	給水量	有収水量			無収 水量	有効 水量	無効 水量
											合計	生活用	その他			
平和郷					262,800				262,800	60,225	12,936	12,936		47,289	60,225	
平和台					76,650				76,650	34,675	10,551	10,551		24,124	34,675	
那珂川水系					339,450				339,450	94,900	23,487	23,487		71,413	94,900	
日光二社一寺			400,000	600,000					1,000,000	610,000	109,000	79,000	30,000	400,000	509,000	101,000
鬼怒川水系			400,000	600,000					1,000,000	610,000	109,000	79,000	30,000	400,000	509,000	101,000
ヒルタウンさつき野						223,800			223,800	215,800	213,550	196,650	16,900	1,150	214,700	1,100
渡良瀬川水系						223,800			223,800	215,800	213,550	196,650	16,900	1,150	214,700	1,100
合 計			400,000	600,000	339,450	223,800			1,563,250	920,700	346,037	299,137	46,900	472,563	818,600	102,100

市町村名	事業名	管種	管種別延長(m)／管種別構成比(%)											
			鑄鉄管	ダクタイル 鑄鉄管	鋼管	石綿 セメント管	硬質塩化 ビニル管	コン クリート 管	鉛 管	ポリエ チレン 管	その他	管路総計	耐震管	法定耐用 年数超
那須町	平和郷	導水管										0		
		送水管				530	1,182					1,712		
		配水管					15,150					15,150		
		合 計	0	0	0	530	16,332	0	0	0	0	16,862	未把握	未把握
		構成比	0.0%	0.0%	0.0%	3.1%	96.9%	0.0%	0.0%	0.0%	0.0%	100.0%		
那須町	平和台	導水管					10					10		
		送水管					88					88		
		配水管					6,871					6,871		
		合 計	0	0	0	0	6,969	0	0	0	0	6,969	未把握	未把握
		構成比	0.0%	0.0%	0.0%	0.0%	100.0%	0.0%	0.0%	0.0%	0.0%	100.0%		
那珂川水系	導水管	0	0	0	0	10	0	0	0	0	10			
	送水管	0	0	0	530	1,270	0	0	0	0	1,800			
	配水管	0	0	0	0	22,021	0	0	0	0	22,021			
	合 計	0	0	0	530	23,301	0	0	0	0	23,831	0	0	
	構成比	0.0%	0.0%	0.0%	2.2%	97.8%	0.0%	0.0%	0.0%	0.0%	100.0%	0.0%	0.0%	
日光市	日光二社 一寺	導水管	400				1,900					2,300		
		送水管	100									100		
		配水管	4,750	950			150			1,550		7,400		
		合 計	5,250	950	0	0	2,050	0	0	1,550	0	9,800	2,100	未把握
		構成比	53.6%	9.7%	0.0%	0.0%	20.9%	0.0%	0.0%	15.8%	0.0%	100.0%	21.4%	
鬼怒川水系	導水管	400	0	0	0	1,900	0	0	0	0	2,300			
	送水管	100	0	0	0	0	0	0	0	0	100			
	配水管	4,750	950	0	0	150	0	0	1,550	0	7,400			
	合 計	5,250	950	0	0	2,050	0	0	1,550	0	9,800	2,100	0	
	構成比	53.6%	9.7%	0.0%	0.0%	20.9%	0.0%	0.0%	15.8%	0.0%	100.0%	21.4%	0.0%	
鹿沼市	ヒルタウン さつき野	導水管					783					783		
		送水管										0		
		配水管		907			8,736					9,643		
		合 計	0	907	0	0	9,519	0	0	0	0	10,426	未把握	未把握
		構成比	0.0%	8.7%	0.0%	0.0%	91.3%	0.0%	0.0%	0.0%	0.0%	100.0%		
渡良瀬川水系	導水管	0	0	0	0	783	0	0	0	0	783			
	送水管	0	0	0	0	0	0	0	0	0	0			
	配水管	0	907	0	0	8,736	0	0	0	0	9,643			
	合 計	0	907	0	0	9,519	0	0	0	0	10,426	0	0	
	構成比	0.0%	8.7%	0.0%	0.0%	91.3%	0.0%	0.0%	0.0%	0.0%	100.0%	0.0%	0.0%	
簡易水道事業合計	導水管	400	0	0	0	2,693	0	0	0	0	3,093			
	送水管	100	0	0	530	1,270	0	0	0	0	1,900			
	配水管	4,750	1,857	0	0	30,907	0	0	1,550	0	39,064			
	合 計	5,250	1,857	0	530	34,870	0	0	1,550	0	44,057	2,100	0	
	構成比	11.9%	4.2%	0.0%	1.2%	79.1%	0.0%	0.0%	3.5%	0.0%	100.0%	4.8%	0.0%	